

*Value Added Tax (Exemption) (Construction of Mother and Child Building)
(Ministry of Health, Community Development, Gender, Elderly and Children)
(Mwananyamala Regional Referral Hospital)*

GOVERNMENT NOTICE NO 230 published on. 20/3/2020

THE VALUE ADDED TAX ACT,
(CAP. 148)

ORDER

(Made under section 6(2))

THE VALUE ADDED TAX (EXEMPTION) (CONSTRUCTION OF MOTHER AND CHILD BUILDING)
(MINISTRY OF HEALTH, COMMUNITY DEVELOPMENT, GENDER, ELDERLY AND CHILDREN)
(MWANANYAMALA REGIONAL REFERRAL HOSPITAL) ORDER, 2020

Citation and
commencement

1. This Order may be cited as the Value Added Tax (Exemption) (Construction of Mother and Child Building) (Ministry of Health, Community Development, Gender, Elderly and Children) (Mwananyamala Regional Referral Hospital) Order, 2020 and shall be deemed to have come into operation on the 26th day of May, 2019.

Exemption

2.-(1) Subject to the conditions specified in paragraph 3 of this Order, and any other conditions as may be specified by the Commissioner, the whole of the Value Added Tax payable on the goods specified in the Schedule to this Order imported or purchased prior to clearance through customs or locally purchased by or on behalf of Mwananyamala Regional Referral Hospital to be used solely in the project for Construction of Mother and Child Building is hereby exempted.

(2) For avoidance of doubt, the goods imported or locally purchased, whether directly by the Government entity or through a contractor shall remain the property of the Government of Tanzania.

Conditions

3. The exemption granted under this Order shall cease to have effect and the Value Added Tax shall become due and be payable as if this exemption had not been made if the said goods or services are used for other purposes or sold or disposed of in any way to another person not entitled to enjoy similar privileges as are conferred under this Order.

*Value Added Tax (Exemption) (Construction of Mother and Child Building)
(Ministry of Health, Community Development, Gender, Elderly and Children)
(Mwananyamala Regional Referral Hospital)*

GN No. 230 (contd.)

Expiry 4. This Order shall expire on the 25th day of May, 2020.

SCHEDULE

(Made under paragraph 2)

GOODS

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (Local or Imported)
1	Substructure			
	Sundries			
a	12mm cement and sand (1:3) external rendering to concrete block wall	93	SM	Local
b	Prepare and apply two coats of black bituminous paints on rendered or concrete surfaces, externally	93	SM	Local
2	FRAME			Local
	Concrete Work			Local
	Vibrated reinforced in-situ concrete grade "25" nominal mix 1:11/2:3 including around reinforcement			Local
a	Beams; horizontal or sloping not exceeding 15 degree from horizontal	74	CM	Local
b	Columns	101	CM	Local
c	150mm thick Horizontal Suspended slab	994	SM	Local
	Reinforcement; bars BS:4449:1969 hot rolled round high yield steel straight or bent			Local
d	20mm Bar	23,700	KG	Local
e	16mm Bar	16,018	KG	Local
f	12mm Bar	24,541	KG	Local

*Value Added Tax (Exemption) (Construction of Mother and Child Building)
(Ministry of Health, Community Development, Gender, Elderly and Children)
(Mwananyamala Regional Referral Hospital)*

GN No. 230 (contd.)

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (Local or Imported)
g	10mm Bar	2,189	KG	Local
h	10 mm Bar	10,345	KG	Local
	Sawn formwork to (Marine plywood) to:			Local
j	Horizontal Soffits of Suspended Slabs	994	SM	Local
k	Vertical Sides of Columns	801	SM	Local
l	Sides and soffits of Horizontal beams	529	SM	Local
m	Edges of suspended slab 75 to 150mm wide	391	SM	Local
3	STAIRS			Local
	CONCRETE WORK			Local
	Reinforced concrete grade "25" including Vibrating around reinforcement			Local
a	Stairs	15	CM	Local
b	150mm Horizontal Suspended landing	39	SM	Local
c	Ditto; sloping over 15 degree from horizon	180	SM	Local
	Reinforcement; bars BS:4449:1969 hot rolled round high yield steel straight or bent			Local
d	16mm Bar	624	KG	Local
e	12mm Bar	1,365	KG	Local
f	8mm Bar	422	KG	Local
	Sawn formwork to:			Local
g	Horizontal soffit of suspended landing	39	SM	Local
h	Sloping soffit of stairs	180	SM	Local
i	Sides and soffits of landscaping beams	27	SM	Local
j	Vertical sides of sloping slabs	108	LM	Local
4	WALLS			Local
a	Block Work	1,148	SM	Local
b	External wall	498	SM	Local
	Concrete blocks to B.S 2028 type A 3.5N per Square			Local

*Value Added Tax (Exemption) (Construction of Mother and Child Building)
(Ministry of Health, Community Development, Gender, Elderly and Children)
(Mwananyamala Regional Referral Hospital)*

GN No. 230 (contd.)

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (Local or Imported)
	millimeter bedded and jointed in cement mortar (1:4)			
c	230 mm wall			Local
d	150mm wall			Local
	Vibrated reinforced concrete grade 25 nominal mix 1:11/2:3			Local
e	25x100mm window cill with wire mesh 2.5mm and formwork	169	M	Local
5	DOORS			Local
	Hardwood materials			Local
a	50x150mm frame with one labor	950	M	Local
	Hardwood door shutter			Local
b	40mm double leaf flash door size 1500x2550mm high comprising 100mm top rail and stile, 150mm wide bottom rail, middle rail and stile, 150mm bottom rail forming two panes filled in with and including 100x25mm thick vertical boarding T & G jointed together to sides of rails and stiles	7	NO	Local
c	Ditto size 1200x2550mm	38	NO	Local
d	40mm single leaf door size 800x2100 mm high comprising 100mm top rail and stile, 150mm wide bottom rail middle rail and stile, 150mm bottom rail forming two panes filled in with and including 100x25mm thick vertical boarding T & G jointed to sides of rails and stiles	50	NO	Local
	Ironmongery; manufactured by Newman Tonks Ltd. Or other equal and approved to hardwood with matching			Local
e	150mm Alluminum butt hinges	210	PRS	Local
f	3 lever mortice lock	95	NO	Local
g	Heavy duty door closer	45	NO	Local
h	150mm long heavy duty closer stopper	95	NO	Local
	Clear Glass			Local

*Value Added Tax (Exemption) (Construction of Mother and Child Building)
(Ministry of Health, Community Development, Gender, Elderly and Children)
(Mwananyamala Regional Referral Hospital)*

GN No. 230 (contd.)

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (Local or Imported)
i	5mm thick glass including beads glass over 0.5m ² nor exceeding 1.00m ²	20	M ²	Local
6	WINDOWS			Local
	Aluminum casement sliding windows with 5mm thick clear glass; fiber and all necessary connections			Local
a	Size 2400x1700mm high	25	NO	Local
b	Ditto size 1500x1700mm high	29	NO	Local
c	Ditto size 900x700mm high	41	NO	Local
	Aluminum fixed windows			Local
d	Size 5750x2700mm high	5	NO	Local
	mild steel grille complete with 25x25mm hollow section, vertical member flat bars spaced at 150mm centre to centre; 25x25mm bottom and top members with including all paints			Local
e	Size 2400x1700mm high	25	NO	Local
f	Ditto size 1500x1700mm high	29	NO	Local
g	Ditto size 900x 700mm high	41	NO	Local
7	ROOFING			Local
a	50x150mm Beam	968	M	Local
b	50x 150mm Rafters	785	M	Local
c	50x 100mm Struts	672	M	Local
d	50x150mm Wall plate	124	M	Local
e	50x50mm Purlins Truss members	1068	M	Local
	Wrot soft wood; 'podo'			Local
f	20mmx250mm Wide wrot hardwood Fascia and barge board, painted	167	M	Local
	28 gauge IT5 corrugated iron roofing sheets fixed to timber purlins with 150mm end laps; 1 ½ corrugations side laps fixed with roofing			Local
g	Roof covering sloping not exceeding 45 degree from the	679	SM	Local

*Value Added Tax (Exemption) (Construction of Mother and Child Building)
(Ministry of Health, Community Development, Gender, Elderly and Children)
(Mwananyamala Regional Referral Hospital)*

GN No. 230 (contd.)

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (Local or Imported)
	horizontal			
h	Ridge/valley capping	83	M	Local
i	Roof ventilation			Local
j	Roof ventilation	6	NO	Local
8	FINISHINGS			Local
	In situ finishing			Local
	Internal plastering in two coats stell troweled to a smooth finish			Local
a	15mm to walls	1304	SM	Local
b	Ditto to sloping softies of stairs cases	219	SM	Local
c	15mm thick plastering ceiling	1325	SM	Local
	External cement and sand (1:4) rendering with approved plasticizer in two coats steel troweled			Local
d	22mm to walls	1155	SM	Local
	Glazed ceramic wall tiles with cushion edges to BS 1281 fixed to backing with cement sand mortar and pointing with white cement			Local
e	300x250x6mm tilling to walls	384	SM	Local
	600x600x8mm PEV matt porcelain floor tiles es Spain fixed backing with cement sand mortar (1:4)			Local
f	Floor and paving	1656	SM	Local
g	150mm thick skirting	528	NO	Local
	Beds and backings			Local
	Cement and Sand (1:4)			Local
a	40mm Beds to receive floor tiles	1656	SM	Local
b	12mm backing to receive wall tiles	384	SM	Local
	Gypsum plasterboard BS 1230 pt. 2 1970 tapered wallboard self tapping galvanized drive screws			Local
c	12mm thick ceiling; horizontal, internal	332	SM	Local
d	Sawn softwood pressure impregnated with preservatives			Local

*Value Added Tax (Exemption) (Construction of Mother and Child Building)
(Ministry of Health, Community Development, Gender, Elderly and Children)
(Mwananyamala Regional Referral Hospital)*

GN No. 230 (contd.)

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (Local or Imported)
e	50x50mm brandering fixed at 600mm centre	1028	M	Local
	Wrot cypress; prime quality selected timber kept clean; prime with tanalith C			Local
f	50x50mm high cornice; two labour	528	M	Local
9	PAINTING AND DECORATIONS			Local
	Internal works			Local
a	Plastered walls	1304	SMS	Local
b	Ditto to sloping softies of stairs cases	219	SM	Local
c	Plastered ceiling	1325	SM	Local
d	Gypsum ceiling	332	SM	Local
	External works			Local
	Prepare and apply one thinned coat and two full coats of weathered guard paint to			Local
e	Rendered surfaces	1155	LM	Local

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (Local or Imported)
	Varnishing; internal work; prepare and apply three coats of clear polyurethane clear varnish; wood surfaces			Local
f	General surfaces	254	SM	Local
g	Frames; linings and associated mouldings 200-300mm girth	950	M	Local

Dodoma,
7th March, 2020

PHILIP I. MPANGO
Minister of Finance and Planning