

GOVERNMENT NOTICE No. 489 Published On. 3/7/2020

THE VALUE ADDED TAX ACT,  
(CAP. 148)

**ORDER**

*(Made under section 6 (2))*

THE VALUE ADDED TAX (EXEMPTION) (CONSTRUCTION OF THEATER BUILDING)  
(MAWENI REFERRAL HOSPITAL IN KIGOMA) ORDER, 2020

Citation and  
commencement

1. This Order may be cited as the Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma) Order, 2020 and shall be deemed to have come into operation on 13<sup>th</sup> May, 2020.

Exemption

2.-(1) Subject to the conditions specified in paragraph 3 of this Order, and any other conditions as may be specified by the Commissioner General of Tanzania Revenue Authority, the whole of the Value Added Tax payable on the goods and services specified in the Schedule to this Order imported or purchased prior to clearance through customs or locally purchased by or on behalf Maweni Referral Hospital in Kigoma to be used solely in the project for Construction of Theater Building at Maweni Referral Hospital in Kigoma is hereby exempted.

(2) For avoidance of doubt, the goods imported or locally purchased, whether directly by the Government entity or through a contractor shall remain the property of the Government of the United Republic.

Conditions

3. The exemption granted under this Order

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

---

*GN. NO. 489 (Contd.)*

shall cease to have effect and the Value Added Tax shall become due and be payable as if this exemption had not been granted if the said goods or services are used for other purposes or sold or disposed of in any way to another person not entitled to enjoy similar privileges conferred under this Order.

Expiry

4. This Order shall expire on 31<sup>st</sup> December, 2020

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

**SCHEDULE**

*(Made under paragraph 2)*

GOODS

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
	GOODS AND SERVICES			
1	Cement	1,257	bag	Local.
2	Sand (5tonne lorry; approximate 4.0m3)	20	trip	Local.
3	Aggregates (5tonne lorry; approximate 4.0m3)	38	trip	Local.
4	Stones (5tonne lorry; approximate 4.0m3)	37	trip	Local.
5	Selected excavated soil	135	trip	Local.
6	Soil treatment solution 20litre bucket	1	buckets	Local.
7	Reinforcement bars 8mm	400	pcs	Local.
8	Reinforcement bars 16mm	450	pcs	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
9	Fabric reinforcement	514	sm	Local.
10	25 x 150mm formwork @ 12feet	100	pcs	Local.
11	Marine Plywood	70	pcs	Local.
12	Nails (3"&4") @50kg	1	Bags	Local.
13	Props	100	pcs	Local.
14	concrete blocks (450 x 230 x 150mm)	1,400	pcs	Local.
15	230mm wide damp-proof course	1	Roll	Local.
16	Damp proof membrane	514	sqm	Local.
17	Oil paint; 4litre tin	3	tin	Local.
18	Sealant rubber flex.	3	tin	Local.
19	Polysulphide sealant.	3	tin	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
	Superstructure			
20	Cement	563	bag	Local.
21	Sand ( 5tonne lorry; Approximate 4.0m <sup>3</sup> )	8	trip	Local.
22	Aggregates ( 5tonne lorry; Approximate 4.0m <sup>3</sup> )	15	trip	Local.
23	Reinforcement bars 8mm	480	pcs	Local.
24	Reinforcement bars 12mm	3	pcs	Local.
25	Reinforcement bars 16mm	365	pcs	Local.
26	25 x 250mm formwork @ 12feet	100	pcs	Local.
27	25 x 150mm formwork @ 12feet	100	pcs	Local.
28	Marine Plywwod	80	pcs	Local.
29	Props	500	pcs	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
30	Nails (3"&4") @50kg	1	Bags	Local.
	Mild steel Black Pipes Balustrade			Local.
31	50mm Dia. Pipe hand rail	120	m	Local.
32	38mm Dia. Pipe balusters	240	m	Local.
33	25mm Dia. Pipe rails	360	m	Local.
	External and Internal Walling			Local.
34	Cement	82	bag	Local.
35	Sand ( 5tonne lorry; approximate 4.0m <sup>3</sup> )	1	trip	Local.
36	Concrete blocks (150mm thick)	2,600	pcs	Local.
37	Concrete blocks (100mm thick)	900	pcs	Local.
	ROOFING			
	Flat Roof			

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
38	Cement	10	bag	Local.
39	Sand ( 5tonne lorry; approximate 4.0m <sup>3</sup> )	1	trip	Local.
40	Gammat water proofing membrane	140	m2	Local.
	Roof structure			
41	Noggin 2"x 2" (50mm x 50mm) of 3.6m long	666	pcs	Local.
42	Wall Plate 3"x 4" (75mm x 100mm) of 3.6m long	30	pcs	Local.
43	Tie Beam 2"x 6" (50mm x 150mm) of 3.6m long	172	pcs	Local.
44	Struts 3"x 4" (75mm x 100mm) of 3.6m long	344	pcs	Local.
45	Rafter 3"x 4" (75mm x 100mm) of 3.6m long	95	pcs	Local.
46	Purlins 2"x 2" (50mm x 50mm) of 3.6m long	250	pcs	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
47	6mm thick plates	4	pcs	Local.
48	Facial Boards Hardwood 1"x 10" (25 x 250 x 3600mm)	30	nos	Local.
49	12 x 180mm bolts	500	nos	Local.
50	16 x 450mm Anchor bolts	90	nos	Local.
	Roof coverings			
	-			
51	Roofing Sheet (Aluzinc IT 5) @ 800mm wide x 1000mm long	867	m	Local.
52	Accessories(hip, ridges and valleys) @ 1500mm	76	pcs	Local.
53	Roofing nails with plastic caps	25	kg	Local.
	Roof Drainage	-	-	
54	150mm Fulbora" cast iron rainwater outlet	8	pcs	Local.
55	125mm Girth U-shaped rain water gutter @ 2400mm	30	pcs	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
56	100mm Diameter down pipes fixed to blockwall with standard holder bat spaced at 1200mm c/c	90	pcs	Local.
57	Extra over for stop ends	8	pcs	Local.
58	100mm Diameter nozzle outlet	8	pcs	Local.
59	110mm Diameter Swan neck 800mm wide	8	pcs	Local.
60	Extra Over for Shoe	8	pcs	Local.
	Doors			
	Hardwood Paneled Shutters			
	-			
61	Panelled doors; 710 x 2450 x 45mm	33	nos	Local.
62	Panelled doors; 810 x 2050 x 45mm	2	nos	Local.
	Hardwood Frame and the like			
	-			
63	50 x 140 x 2500mm Hardwood frames,transomes	80.00	nos	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
	& Mullion			
64	15 x 40 x 2500mm Hardwood fixing architrave	90.00	nos	Local.
65	15 x 25 x 2500mm Hardwood stops	80.00	nos	Local.
66	15 x 10 x 2500mm Thick glazing beads	25.00	nos	Local.
	Glass			
67	6mm thick ordinary quality	19.00	sqm	Local.
	Iron Mongery			
68	Mortice locks; two levers	35.00	nos	Local.
69	Aluminum hinges; 150mm long	52.50	pairs	Local.
70	Door floor rubber stops	35.00	nos	Local.
	Grills			
61	12mm dia. Mild steel burglar bars	20.00	pcs	Local.
	Miscelenous costs			
62	Nails (3" & 4") @ 50kg per bag	1.00	Bag	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
63	Sand paper	1.00	Roll	Local.
64	Varnish (4 tins carton)	1.00	Carton	Local.
65	Glue	3.00	Kg	Local.
66	Red oxide paint; (4 tins carton)	1.00	Carton	Local.
67	Oil paint; (4 tins carton)	1.00	Carton	Local.
68	Standard Thinner	1.00	Gallon	Local.
69	75mm diameter door signages	4.00	pcs	Local.
	<u>Finishings</u>			
	Plastering, Rendering & Floor Screeding			
	Cement	600	bag	Local.
70	Sand ( 5tonne lorry; approximate 4.0m <sup>3</sup> )	18	trip	Local.
71	Gypsum powder @25kg (ex-Tanzania B.B.G	150.00	Bags	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
72	White cement (externally) @ 40kg	50.00	Bags	Local.
73	Emulsion paints for mixing with white cement& gypsum powder; bucket 20litres@	50.00	Buckets	Local.
	Tiles			
74	tiles 400 x 400 x 8mm thick porcelain tiles	514	sqm	Local.
75	tiles 300 x 300 x 6mm thick ceramic tiles	145	sqm	Local.
76	Self levelling epoxy floor slury (Provisional)	100	sqm	Local.
77	Cement	94	bag	Local.
78	Sand ( 5tonne lorry; approximate 4.0m <sup>3</sup> )	1	trip	Local.
	Gypsum Ceiling Board			
79	Gypsum board ceiling (1200 x 2400mm) (ex-Thailand)	196	pcs	Local.
80	Paper Gypsum cornices @ 2400mm	80	pcs	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
81	50 x 50 x 3000mm timber for brandering	2,570	m	Local.
82	Gypsum powder @25kg (Andika for fixing gypsum board)	30.00	Bags	Local.
83	Emulsion paints for mixing with white cement& gypsum powder; bucket @ 20litres	80.00	Buckets	Local.
84	Fiber tape	5.00	Roll	Local.
85	Spartra	10.00	pc	Local.
86	Nails 3" for brandering	1	Bag	Local.
87	Gypsum Screws	15	Boxes	Local.
	Electrical And Fire Detection Installations			
	FLOOR PLAN			
	Power Distribution.			
88	12Ways TPN distribution board DBG with integral 100A/300mA RCD incomer and final circuit MCBs of 10A SP (9No),20A SP(20No) and 32A SP(7No) as ABB	1	nr	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
	TYPE or APROVED EQUIVALENT.			
89	4C x 25mm <sup>2</sup> Cu, PVC/SWA/ PVC cable from Nearest TANESCO POLE to floor distribution board DBG	100	m	Local.
90	1C x 16mm <sup>2</sup> Cu,PVC Green/Yellow earth cable.DBG	100	m	Local.
91	100mm diameter heavy gauge PVC Pipe	100	m	Local.
	Small Power Distribution			
92	25mm diameter heavy gauge PVC conduits concealed under walls and roof floors from distribution Boards to all power outlet points	1,000	m	Local.
93	Single core 2.5 sqmm PVC copper cables from distribution Boards to all power outlet points	3,000	m	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
94	Trunking Installations;3-compartment PVC trunking 170 x 50mm to be recessed on walls(flush) and installed at skirting level complete with all necessary fixing accessories as MK	45	m	Local.
95	2 x 13A raw power switched socket outlet complete with back box as Legrand or approved equivalent	40	nr	Local.
96	Telecommunication point back box	7	nr	Local.
97	20A DP switch for A/C and W/H as Legrand or approved equivalent	20	nr	Local.
	Light Fittings			
98	20mm diameter heavy gauge PVC conduits concealed under walls and roof floors from distribution Boards to all lighting outlet points and fixtures	2,000	m	Local.
99	Single core 1.5 sqmm PVC copper cables from distribution Boards to all lighting outlet points	6,000	m	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
100	LIGHTING TYPE A: Ceiling surface mounted line light with fluorescent 2x16W (LED ECOMAX T8 BATTEN), product no (LED-E-T8-1200MM-16W-3000K-CT BY OPPLER TYPE or approved equivalent	35	nr	Local.
101	LIGHTING TYPE B: Ceiling surface mounted line light with fluorescent 1x16W (LED ECOMAX T8 BATTEN), product no (LED-E-T8-1200MM-16W-3000K-CT BY OPPLER TYPE or approved equivalent	13	nr	Local.
102	LIGHTING TYPE C: Surface mounted downlight decorative bulkhead fittings for (LED CEILING/WALL LAMP ) with product no.HC420 23W5700K BY OPPLER TYPE or approved equivalent	32	nr	Local.
103	LIGHT TYPE D: Surface mounted downlight decorative bulkhead fittings for (LED CEILING/WALL LAMP ) with product no.HC350 16W 5700K WHITE BY OPPLER TYPE or approved equivalent	10	nr	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
104	LIGHTING TYPE E: Surface mounted downlight decorative bulkhead fittings for (LED CEILING/WALL LAMP ) with product no.HC480 22W 5700K STAR DIAMOND BY OPPLER TYPE or approved equivalent	5	nr	Local.
105	LIGHTING TYPE F: Jupiter wall light, stainless steel wall light with white polycarbonate diffuser,IP65 rated, recommended for use with max 11W screw GLS BULB, complete with lamp by OPPLER TYPE or approved equivalent.	13	nr	Local.
106	Single sided Exit light, with 3hrs duration emergency bulkhead for 8W T16(T5), as opple type or approved equivalent	4	nr	Local.
107	One way 1 gang light switch as Legrand or equivalent	23	nr	Local.
108	One way 3 gang light switch as Legrand or equivalent	5	nr	Local.
109	Two way 1 gang light switch as Legrand or equivalent	18	nr	Local.
	MAIN SUPPLY			

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
110	100A TPN automatic changeover switch comprising of two 4-pole electrically and mechanically interlocked 100A motorised MCCB complete with controller	1	nr	Local.
111	4C x 25mm <sup>2</sup> Cu,PVC/SWA/PVC cable from Nearest TANESCO pole,generator passing through changeover switch to main distribution board(MDB)	126	m	Local.
112	1C x 16mm <sup>2</sup> Cu,PVC Green/Yellow earth cable.	126	m	Local.
113	All for complete earthing of the Electrical System to IEE standards.	1	sum	Local.
114	Allow for testing and commissioning of the entire Installation	1	sum	Local.
115	Allow preparation of four copies of " Installed Drawings" and operating manuals.	1	sum	Local.
116	Allow for maintenance of electrical equipments and fire alarm during defect liability	1	sum	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
117	Supply and installation of copper earth 4ft rod, earth rod connector and cable lugs for 35sqmm cable	4	sum	Local.
118	Electrical Contractor's attendance and liasing fees with Tanesco	1	sum	
119	Manhole of 900mm x 900mm inside 0,8 m deep (red soil ), with painted cover 2 mm thick, for 4c armored cable up to 150 mm <sup>2</sup>	2	nr	Local.
120	Supply and install the PERKINS/MANTRAC generator set of 3 Phase, 45kVA, 50Hz – diesel generator sets with sound attenuated, auto start generator set and all features required for standby applications conveniently packaged together.	1	nr	Local.
121	45A Single phase Isolator for outdoor unit.	3	nr	Local.
122	3C x 10mm <sup>2</sup> Cu,PVC/SWA/ PVC cable from distribution board to outdoor unit	80	m	Local.
123	Provisional for power connection to the new buiding	1	item	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
	FIRE DETECTION & ALARM SYSTEMS			
124	CONVENTIONAL fire control panel, (2loops, 4 zones fire panel c/w batteries {72 hour standby}	1	nr	Local.
125	Smoke detectors as AP6-FT8 CONVENTIONAL complete with Sounder base	23	nr	Local.
126	Heat detectors as AP6-FT8 CONVENTIONAL complete with Sounder base	1	nr	Local.
127	Breakglass CONVENTIONAL, complete with surface -box as FML-200R	3	nr	Local.
128	Firebell/CONVENTIONAL sounder, 6inch as ABB624	3	nr	Local.
129	Firebell/Conventional FLASHING SOUNDER, 6inch as ABB624	4	nr	Local.
130	Fire resistant cable 1.5sqmm,twin with earth wire	800	m	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
	ICT INSTALLATIONS			
	Supply, install, test and commission the following:			
131	Dual RJ 45 wall face plate complete with modules, spring shutter and cabling field for Cat 6 cabling	7	nr	Local.
132	4-pair unshielded twisted pair cable(UTP),Cat6	305	m	Local.
133	24 ports Rj45 data and voice patch panel	1	nr	Local.
134	24 ports Rj45 Cisco Switch,cat 6	1	nr	Local.
135	1m RJ45 patch code	14	nr	Local.
136	Patch guide (cable organizer)	1	nr	Local.
137	9U voice and data cabinet with 2 heat extract fans and 6 ways power distribution unit (PDU) and glass door.	1	nr	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
138	Provide adequate earthing to voice cabinet as per IEE Regulations	1	item	Local.
139	3m RJ45 patch code	14	nr	Local.
	PABX AND ACCESSORIES			
140	IP PABX requiring up to 24 concurrent calls and 50 users offering 16 phone ports, it supports FOX, ISDN,BRI Lines GSM/UMTS network ,VoIP and Audio in/out. Including all accessories for complete function of the system	1	nr	Local.
141	Operator console for inquire desk	1	nr	Local.
142	Dual port IP telephone handset	6	nr	Local.
143	1.5kVA -SP ,UPS and Back up Batteries	1	Lot	Local.
	PRELIMINARIES			
144	Allow for preparation of shop drawings	1	Item	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
145	Allow for preparation of 3 sets of as built drawings and operation manuals	1	Item	Local.
146	Allow for maintenace of ICT services during deffect liability period	1	Item	Local.
147	Allow for testing and commissioning of entire installation	1	Item	Local.
148	Allow for attendance and liasing fee for TTCL connection	1	Item	Local.
149	Allow connection from TTCL	1	item	Local.
150	Dual RJ 45 wall face plate complete with modules,spring shutter and cabling field for Cat 6 cabling	10	nr	Local.
151	4-pair unshielded twisted pair cable(UTP),Cat6	6	m	Local.
152	24 ports Rj45 data and voice patch panel	3	nr	Local.
153	24 ports Rj45 Cisco Switch,cat 6	1	nr	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
154	1m RJ45 patch code	20	nr	Local.
155	Patch guide (cable organizer)	5	nr	Local.
156	15U voice and data cabinet with 2 heat extract fans and 6 ways power distribution unit (PDU) and glass door.	1	nr	Local.
157	Provide adequate earthing to voice cabinet as per IEE Regulations	1	item	Local.
158	3kVA -UPS and Back up batteries	1	Lot	Local.
159	3m RJ45 patch code	20	nr	Local.
	<b>PABX AND ACCESSORIES</b>			
160	IP PABX requiring up to 24 concurrent calls and 100 users offering 16 phone ports, it supports FOX, ISDN,BRI Lines GSM/UMTS network ,VoIP and Audio in/out. Including all accessories for complete function of the system	1	nr	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
161	Operator console for inquire desk	1	nr	Local.
162	Dual port IP telephone handset	10	nr	Local.
163	1.5kVA -SP ,UPS and Back up Batteries	1	Lot	Local.
	Air Conditioning Installations			
	Split Types Units			
	Wall mounted cooling only Indoor/ Fan Coil Unit:			
164	Cooling capacity:7.1kW	2	nr	Local.
165	Cooling capacity:5.2kW	3	nr	Local.
166	Cooling capacity:3.5kW	3	nr	Local.
	Refrigerant Pipping:			
167	6.35mm diameter phosphorus, deoxidized seamless fittings and accessories	55	m	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
168	Ditto but 9.52mm	18	m	Local.
169	Ditto but 12.7mm	37	m	Local.
170	Ditto but 15.88mm	12	m	Local.
	Inter-unit wiring and Power Supply Cable			
171	Supply and install electrical cable of 2.5 mm <sup>2</sup> including all necessary accessories from DP Switch to the respective indoor and outdoor units.	1	Item	Local.
	Condensate drainage piping			
172	Supply and install condensate drainage pipe Upvc complete with all associated fittings.support inclusive.			Local.
173	25 mm dia with insulation	100	m	Local.
174	AUTOMATIC Voltage Switcher, 230V, 50HZ, 15mps for the above Air Condition units.	8	nr	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
	MECHANICAL VENTILATION			
	Single Package unit			
175	Cooling Capacity 10.5kW, Air Flow rate 566L/s.	3	nr	Local.
	Ductwork			
	Supply Air Duct			Local.
176	315 x 250mm	24	m	Local.
177	160x125mm	12	m	Local.
	Return Air Duct			
178	315 x 250mm	22	m	Local.
179	250X200mm	8	m	Local.
	DIFFUSERS			

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
180	Supply, install, test and commission the linear return grills 850 x 125 mm returning 475l/s . Shouls have 10 micro filter, stanles steel perforated grill and pressure balancing damper.	6	nr.	Local.
	Sound attenuator			
181	Supply and install sound attenuators for package units in both supply and return ducts.The type of sound absorber shall be in accordance with the specification provided with the supplier of unit.			Local.
182	315x250mm	3	m	Local.
183	250x200mm	3	m	Local.
184	160x125mm	3	m	Local.
	Supply balancing volume control damper (VCD) in supply and return air ducts branches as specified on the drawings, with size			Local.
185	VCD 250x200mm	3	nr	Local.
186	VCD 160x125mm	3	nr	Local
	Fire Dampers			

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
187	Supply fire dampers in both supply and return air ducts (various sizes)			
188	250 x 200mm	3	nr	Local.
189	160 x 125mm	3	nr	Local.
	Toilet Extract Fan			
190	Supply and install inline Roof/Wall fan for toilet extract system, complete with standby unit and automatic change over switch, ducting, voice control dumper and all necessary accessories.			
	a)300 m3/hr	1	nr	Local.
	<u>Bends/Reducers etc</u>			
	-			
191	Allow for bends, reducers, supporter etc to accommodate for above ducting installation system	1	Item	Local.
	Preliminary			

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
192	Supply "AS BUILT DRAWINGS" as per specification	1	Item	Local.
193	Supply "OPERATION AND MAINTENANCE MANUALS" as per specification	1	Item	Local.
194	Allow for shop drawings as specified	1	Item	Local.
195	Testing and Commissioning report as specified.	1	Item	Local.
	Plumbing Engineering Installations			
	External/ Core Services			
196	Supply and install 40mm diameter HDPE pipe, complete with fittings and supporting brackets for transferring water to roof water tank	122	m	Local.
197	Supply and install 40mm diameter gate valves to support the above installations	4	nr	Local.
198	Supply and install 40mm diameter non-return valves to support the above installations	2	nr	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
	Storage water tank			
199	Supply, install, test and commission Glass reinforced plates (GRP) roof water storage tank with capacity of 25m <sup>3</sup> . The tank dimensions: 5x5x1.m (LxWxH)	1	nr	Local.
200	Allow for connection from the existing water supply main pipe to roof water storage tanks, including supply pipe, float switch, water meter, valves and other associated fittings.	1	Item	Local.
201	Allow for maintenance of equipments during defect liability period	1	item	Local.
202	Allow preparation of three copies of " Installed Drawings" and operating manuals for all equipment's as specified	1	item	Local.
203	Allow for connection of the waste system to sewer or septic system	1	item	Local.
	COLD WATER PIPING			

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
204	Supply, install, test and commission PPR pipe (DiZAYN GROUP) and tubing class "6" to BS 4554 with screwed and socketed joints to BS 143 and 126 of approved manufacture.			Local.
	PIPES			
205	20mm diameter	60	m	Local.
206	25mm diameter	58	m	Local.
207	32mm diameter	90	m	Local.
	90° Elbow			
208	25mm	29	nr	Local.
209	20mm	29	nr	Local.
210	32mm	6	nr	Local.
	Tee			
211	25mm	24	nr	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
212	20mm	20	nr	Local.
213	32mm	6	nr	Local.
	Reducer			
214	32/25	6	nr	Local.
215	25/ 20	22	nr	Local.
216	40/32	1	nr	Local.
	Gate Valve; B.S. 1010; Part 2: wheel head; polished by manufacturer; joints to pipe; both ends screwed male iron			Local.
217	40mm	2	nr	Local.
218	32mm	6	nr	Local.
219	25mm	6	nr	Local.
220	20mm	29	nr	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
221	Supply and install 15mm diameter flexible pipe connectors to wash hand basin (WHB), water closet (WCs), etc.	29	nr	Local.
222	Allow for Supply and install extra pipe fittings and accessories for the above water supply piping	1	Item	Local.
	WASTE WATER			
	External pipe work			
223	Supply and install 150mm uPVC pipe class "B" according to BS 8301 - 1985 complete with associated fittings	82	m	Local.
224	Allow for Construction of foul/waste water manholes of internal dimension 600x600mm with invert level not exceeding 1000mm comprising 200mm plain concrete grade "C" bed 230mm block wall plastered internally as per specification and drawings including heavy duty cast iron cover to match with external paving.	15	nr	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
225	Allow for Construction of 300X300mm standard gully trap as per specification and drawings including heavy-duty cast-iron cover to match with external paving.	10	nr	Local.
226	Excavate trench not exceeding 1000 mm deep and average 500mm wide for laying sawerage pipe to the sewer line not exceeding 200mm diameter including backfilling	140	m	Local.
227	Supply and install Galvanized steel wire ballon set on top of vent pipe and covered with mosquito gauze, 100mm diameter	6	nr	Local.
	Allow for construction of the septic tank 4.5mx 2.5mx 2.0m	1	Item	Local.
228	Allow for construction of the soak away pit of 3m diameter size.	2	Item	Local.
	Rain water pipework installation as per specification and drawings.Note: Rainwater pipe should be uPVC white colour			Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
229	Supply, install, test and commission 100mm diameter uPVC down pipe, complete with fittings and fixtures (Vertical pipework)	52	m	Local.
230	Supply, install, test and commission 150mm diameter uPVC water gutter, complete with fittings and fixtures (Horizontal pipework)	110	m	Local.
231	Allow for connection of storm water to water tanks of 5000 Liters simtank and all necessary fittings	2	Item	Local.
	Soil and vent pipe work			
232	Supply and install all above ground/exposed of class "B" to BS 8301 - 1985 uPVC pipe complete with associated fitting including chasing walls, pipe supports and necessary decoration for exposed pipe work pipes: pipes;fixing with holders to backgrounds requiring plugging			
	100mm diameter, uPVC pipe	50	m	Local.
	75mm diameter ,upvc pipe	30	m	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
	50mm diameter, Upvc pipe	62	m	Local.
	40mm diameter, Upvc pipe	45	m	Local.
	ELBOWS,90			
	100mm diameter, UPVC	12	nr	Local.
	75mm diameter ,upvc pipe	8	nr	Local.
	50mm diameter, uPVC	25	nr	Local.
	ELBOWS 45			
	100mm diameter, UPVC	12	nr	Local.
	50mm diameter,Upvc	8	nr	Local.
	40mm diameter,uPVC	28	nr	Local.
	Supply, install, test and commission Floor drain, 50mm diameter outlet, uPVC	5	nr	Local.
	SANITARY APPLIANCES			

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
234	Supply, install, test and commission Asian type WC;as to RAK or equal approved Close coupled floor standing with complete combination wash down outlet, dual flush cistern 2.5litres or less for half flush and 3.5litres or less for full flush, seat and cover and all accessories. "P" or "S" trap pans; bedding uotlets in mastic; fixing with brass screws to backgrounds requiring plugging.	1	nr	Local.
235	Supply, install, test and commission European type WC;as to RAK or equal approved Close coupled floor standing with complete combination wash down outlet, dual flush cistern 2.5litres or less for half flush and 3.5litres or less for full flush, seat and cover and all accessories. "P" or "S" trap pans; bedding uotlets in mastic; fixing with brass screws to backgrounds requiring plugging.	4	nr	Local.
236	Supply, install, test and commission White vitreous china Hand wash basin as to RAK or equal approved ;Pedestrial type wall mounted ; complete with tap mixer capable to discharge water at a flow rate of 2litres/min. or less. Fixing with screws to backgrounds requiring plugging	12	nr	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
237	Shataff;ABS chrome with supreme Hose and wall holder as to RAK or equal approved fixing with brass screws to backgrounds plugging	5	nr	Local.
	Soap dispenser;glass wall mounted as to RAK or equal approved fixing with brass screws to backgrounds plugging	12	nr	Local.
238	Mirrors; overall size 1200 x 900mm high, fixed to wall with CP screw and caps	12	nr	Local.
239	Toilet paper holder;chrome as to RAK or equal approved fixing with brass screws to backgrounds plugging	5	nr	Local.
240	Supply , install , test and commision hand dryer as mediclinic brand or equal approved	5	nr	Local.
241	Supply and install Stainless steel wash sink ; complete with two Stainless-steel sink mixers with discharge flow rate of 4litres/min for scrubbing,cssd, sluice & operation rooms complete with connecting accessories, fixing with screws to	6	nr	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
	backgrounds requiring plugging			
242	Supply and install Stainless shower tray and its shower closure(shower cubical) complete with connecting accessories, fixing with screws to backgrounds requiring plugging	2	nr	Local.
243	Supply and install wate heater of 25 liters of ARISTON or equal approved.	4	nr	Local.
245	Supply and install towel rail	2	nr	Local.
	PORTABLE FIRE EXTINGUISHER			
246	Supply, install, test and commission Fire extinguisher bottles ,by NAFFCO or equal approved of Dry powder (ABC), 9kg monted on wall	2	nr	Local.
247	Supply, install, test and commission Fire extinguisher bottles,by NAFFCO or equal approved of Carbon dioxide (Co <sub>2</sub> ), 5kg mounted on wall	2	nr	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
	LABORATORY GASES INSTALLATIONS			
	Piping			
248	Supply install, test and commission in good working condition copper pipes and fittings for medical gases that comply with BS EN ISO 7396-1:2016 and ASTM A312M; Pipes and fittings in running length fixed to backgrounds requiring plugging			
	20mm diameter, copper pipe	25	m	Local.
	15mm diameter, copper pipe	12	m	Local.
	10mm diameter, copper pipe	10	m	Local.
	8mm diameter, copper pipe	30	m	Local.
	Elbow			
	20mm diameter	8	nr	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
248				
	15mm diameter	8	nr	Local.
	10mm diameter	8	nr	Local.
	Tee			
	20mm diameter	4	nr	Local.
	15mm diameter	4	nr	Local.
	10mm diameter	4	nr	Local.
	Reducer			
	20/15mm	12	nr	Local.
	Reducer			
	15/10mm	12	nr	Local.
Gas control Valve				

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
	20mm diameter	2	nr	Local.
	15mm diameter	3	nr	Local.
	10mm diameter	4	nr	Local.
	8mm diameter	12	nr	Local.
	Medical Gas cylinder			
249	Supply, install, test and commission medical gas storage cylinder with capacity of 8 Liters	2	nr	Local.
	High pressure Hose			
250	Supply and install flexible high-pressure hose rubber/plastic with inner diameter of 8mm	12	nr	Local.
	Gas taping point/ Gas Control box/ Distribution panel			
251	Supply, install, test and commission gas taping point for medical gas that includes pressure regulator, valves, flow meter ect.	12	nr	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTITY (QTY)	UNIT OF MEASURE	PLACE OF PURCHASE OF ITEMS (local or imported)
252	Supply, install, test and commission manifold, automatic change over panel, central alarm panel complete signal cables for medical gas	1	Item	Local.
253	Allow for copper pipe fittings i.e elbow, tee, reducer, coupler	1	Item	Local.
254	Allow for maintenance of equipments during defect liability period	1	Item	Local.

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni Referral Hospital in Kigoma)*

*GN. NO. 489 (Contd.)*

S/N	ITEM DESCRIPTION	QUANTIT Y (QTY)	UNIT OF MEASUR E	PLACE OF PURCHAS E OF ITEMS (local or imported)
255	Allow preparation of three copies of " Installed Drawings" and operating manuals for all equipment's as specified	1	Item	Local.
256	PAINTING AND DECORATION			
	Emulsion Paints	25	Buckets	Local.
	Wash n wear	15	Buckets	Local.
	Weather guard	8	Buckets	Local.
	Sand paper	1	Roll	Local.
	Brushes	10	pcs	Local.
	Roller Brushes	10	pcs	Local.
	Varnish	10	tin	Local.
	Red oxide paint; 4litre tin	5	tin	Local.
	Oil paint; 4litre tin	5	tin	Local.
	Standard Thinner	5	Gallon	Local.

Dodoma,  
19<sup>th</sup> June, 2020

PHILIP .I. MPANGO  
*Minister of Finance and Planning*

*Value Added Tax (Exemption) (Construction of Theater Building) (Maweni  
Referral Hospital in Kigoma)*

---

*GN. NO. 489 (Contd.)*